


Date: 9/2/2019  
Project: Estimate 1  
Job# RS00060



Customer Name: Barbara Dickerson RS-0219  
Sales Person: Ray Smith  
Address: 12918 W. Ashwood Dr.  
Surprise, AZ 85375

**Location: Kitchen**

**CABINETRY:**

KITCHEN CABINETS >> Dynasty Cabinetry >> DYNASTY CABINETS>>Other NOTES: DYNASTY VAIL CABINETS, ELEMENTAL WHITE OPAQUE STAIN ON MAPLE WOOD, EDGE PROFILE W, SLAB DRAWER FRONT, INSTALLED WITH TAX = \$13,900.	1.00
--	------

**CLEAN UP:**

15 YD DUMPSTER	1.00
CLEANING SERVICE	1.00

**CONCRETE:**

FLOOR CUTTING >> CHANNEL CUT FLOOR TO RUN 220V LINE TO RANGE AND 110V LINE TO ISLAND.>>Other	1.00
FOUNDATION >> 18X18 FOUNDATION	20.00
FOUNDATION >> 18X18 POURED FOOTING WITH STEM WALL	20.00
FOUNDATION >> 8 X 42 FOUNDATION	20.00

**COUNTER TOP:**

SLAB FABRICATION >> QUARTZ COUNTER TOPS>>Other NOTES: LG VIATARA CLARINO COUNTER TOPS, NO SPLASHES, 1 1/2" DOUBLE ROUNDOVER 3/8" EDGING, PREP. FOR U.M. SINK, INSTALLED WITH TAX = \$8,975.	1.00
---	------

**DEMOLITION:**

CABINETS AND COUNTERS >> TEAR OUT AND REMOVE CABINETS AND COUNTER TOPS.>>Other	1.00
WALL >> REMOVE NON BEARING WALL	17.00

**ELECTRICAL:**

OUTLETS >> OUTLET(S) IN ISLAND	3.00
OUTLETS >> WALL OUTLET	3.00
SWITCHES >> 3 WAY SWITCH	1.00
SWITCHES >> STANDARD SWITCH	2.00
LIGHTING >> LED >> LED STRIP LIGHT	6.00
APPLIANCES >> RUN 220V LINE TO SLIDE IN RANGE IN ISLAND>>Other	1.00

**FINISH TRIM:**

GENERAL TRIM >> BASE MOLDING STANDARD 3 IN	20.00
--	-------

**HARDWARE:**

CABINET HARDWARE >> TOP KNOBS M1170BSN BRUSHED STAIN NICKEL PULLS>>Other	1.00
---	------

**PAINTING / STAINING:**

INTERIOR PAINTING >> PAINT CEILING ONE COAT WITH CLIENT SUPPLIED PAINT	300.00
INTERIOR PAINTING >> TOUCH UP PAINTING WITH CLIENT PROVIDED PAINT	24.00

**PLUMBING:**

KITCHEN PLUMBING >> SINK: >> LABOR ONLY INSTALL SINK TO EXISTING LOCATION, NEW P TRAP AND ANGLE STOPS INCLUDED	1.00
KITCHEN PLUMBING >> FAUCET >> LABOR ONLY FAUCET IN COUNTER TOP	1.00
KITCHEN PLUMBING >> SINK: >> FREE SINK>>Other NOTES: BLANCO SILGRANIT UNDERMOUNT STANDARD SINK. COLOR AND SHAPE TO BE SELECTED.	1.00

**PROJECT PREPARATION:**

SITE PREPERATION >> DUST CONTROL	1.00
----------------------------------	------

**SUN CITY:**

MISC>>Other	1.00
-------------	------

**TILE, STONE, PORCELAIN OR CERAMIC:**

TILE >> WALL TILE LABOR ONLY >>Other	1.00
TILE >> WALL TILE MATERIAL>>Other	1.00
COUNTER TOP OR BACK SPLASH >> WESTERN PACIFIC TILE OCEANS CORRAL BRICK VH5795-1>>Other	1.00

**WALL & CEILING DRYWALL:**

PATCH WORK >> REPAIR WALL & CEILING FROM DROP REMOVAL	17.00
---	-------

**Sub Total: 38,442.82**