Composite SOW by Section





Customer Name: First Name Last Name

Job Number: TT05004

Estimate Name: Estimate 7

Section: PROJECT PREPARATION				
Location	Item Name	Short Notes	It	em Status
Bathroom- Master 1	SITE PREPERATION >> DUST CONTROL >>			
Bedroom- 1	SITE PREPERATION >> DUST CONTROL >>			
			Sub Total:	\$777.00

Section: DEMOLITIO	N		
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	TILE >> REMOVE FLOOR TILE under 500 ft >>		
Bathroom- Master 1	TILE >> REMOVE WALL TILE >>		
Bathroom- Master 1	TILE >> LITE FLOOR GRINDING SMALL PREP >>		
Bathroom- Master 1	CABINETS AND COUNTERS >> REMOVE CABINET AND COUNTER TOP >>		
Bathroom- Master 1	MIRROR >> REMOVE WALL MIRROR OVER 4 X 6FT IN SIZE >>		
Bathroom- Master 1	MEDICINE CABINET >> REMOVE MEDICINE CABINET >>		
Bathroom- Master 1	DOORS WINDOWS >> REMOVE GLASS BLOCKWINDOW>>Other		
Bathroom- Master 1	INTERIOR >> REMOVE TUB >>		
Bathroom- Master 1	TILE >> DUST FREE PORCELAIN OR CERAMIC REMOVAL AND DISPOSAL >>		
Bedroom- 1	TILE >> DUST FREE PORCELAIN OR CERAMIC REMOVAL AND DISPOSAL >>		
Bedroom- 1	TILE >>Test Other>>Other		Item Deleted (Change Order 1, 4/15/2021)
Bathroom- Master 1	TILE >>Test Other>>Other		Item Deleted (Change Order 3, 4/15/2021)
		Cub Totali	\$4 47E 64

Sub Total: \$4,475.61

		NTR	

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	WALL ALTERATION >> CREATE OPENING IN EXTERIOR WALL FOR DOOR OR WINDOW >>		
Bathroom- Master 1	WALL ALTERATION >> FRAME NEW EXTERIOR OPENING FOR DOOR OR WINDOW >>		
Bathroom- Master 1	WALL ALTERATION >> CLOSE IN WINDOW OR DOOR OPENING (FRAMING ONLY) >>		

Sub Total: \$892.96

Section: E	LECTRICAL
------------	-----------

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	SWITCHES >> CEILING FAN SWITCH >>		
Bathroom- Master 1	LIGHTING >> REPLACE WALL LIGHT LABOR ONLY IN EXISTING LOCATION >>		
Bathroom- Master 1	CEILING FAN >> REPLACE EXISTING CEILING FAN SAME LOCATION LABOR ONLY >>		
		Sub Total:	\$641.63

Section: CABINETRY

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	MEDICINE CABINET >> LABOR TO INSTALL RECESSED MED CAB IN EXISTING OPENING >>		
Bathroom- Master 1	BATH CABINET >> DYNASTY PURITAN DOOR STYLE, NATURAL FINISH ON MAPLE WOOD, SLAB DRAWER FRONT, EDGE PROFILE W, INSTALLED WITH TAX = \$5,275.>>Other		

Sub Total: \$5,441.09

Section: COUNTER TOP

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	SLAB FABRICATION >> 2CM GRANITE COUNTER TOP, 1 1/2" DOUBLE ROUND OVER EDGE, 4" SPLASHES, PREPARATION FOR 2 UNDERMOUNT BOWLS, INSTALLED.>>Other	REMNANT GRANITE AT \$1,275.	
Bathroom- Master 1	SLAB FABRICATION >> OPTION A: 2CM ST. CECILIA GRANITE TOP = \$1,975.>>Other		

Sub Total: \$1,275.00

Section: TILE, STONE, PORCELAIN OR CERAMIC

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	SHOWER AREA >> Cement board is the most durable, trouble-free tile backer for tub surrounds, showers, floors and all other wet areas. Its made from cement and sand, and is reinforced by fiberglass mats on both sides, so it's impervious to water. Contractor will use appropriate product for area brand names vary. >>		
Bathroom- Master 1	SHOWER AREA >> NICHE FOR SHAMPOO BOTTLE standard 14 x 16 >>		
Bathroom- Master 1	SHOWER AREA >> SOAP NICHE IN WALL >>		
Bathroom- Master 1	SHOWER AREA >> STRAIGHT INSTALL SHOWER WALLS LABOR >>		
Bathroom- Master 1	TILE >> TILE FLOOR STRAIGHT, STAGGER, OR RUNNING BOND OVER 1000 SQ FT LABOR ONLY >>		
		Sub Total:	\$5.723.75

Section: CLEAN UP

Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	15 YD DUMPSTER >>		

		Sub Tota	: \$425.50
Section: CONCRETE			.,
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	FILL SUNKEN INTERIOR FLOOR >> FILL IN SUNKEN TUB OR SHOWER >>		
Bathroom- Master 1	FILL SUNKEN INTERIOR FLOOR >> SMOOTH FLOAT AND TROWEL >>		
Section: HARDWARE		Sub Tota	: \$1,248.54
	Item Name	Chart Nata	Itom Status
Location Bathroom- Master 1	BATHROOM >> LABOR ONLY >> INSTALL CLIENT SUPPLIED BATHROOM ACCESSORIES (towel bars, hooks etc) >>	Short Notes	Item Status
		Sub Tota	: \$101.75
Section: PERMITS			
Location	Item Name	Short Notes	Item Status
Hallway- 1	test item >>		
Hallway- 1	CITY PERMIT KITCHEN >>		
		Sub Tota	: \$444.70
Section: WINDOWS			-,
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	VINYL >> SLIDING BEIGE VINYL DUAL PANE WINDOW>>Other	Sub Tota	: \$300.00
Section: GRAB BARS			.,
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	SHOWER BARS >> 12 TO 18 INCH BAR VERTICLE >>		
Bathroom- Master 1	SHOWER BARS >> L Shaped Grab Bars 16 x 32, 24 x 36, 24 x 48 >>		
Bathroom- Master 1	TOILET AREA >> SIDE BAR >>		
Section: MIRROR		Sub Tota	\$608.65
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	FLAT WALL MIRROR >> WALL MIRROR ROUNDED EDGE >>	<u> </u>	nom otatao
		Sub Tota	: \$601.38
Section: PAINTING / S	STAINING		
Location	Item Name	Short Notes	Item Status
Bathroom- Master 1	INTERIOR PAINTING >> PAINT INTERIOR WALLS ONE COLOR (Wall sq ft under 300ft) >>		
		Sub Tota	: \$420.99
Section: PLUMBING			
Location	Item Name	Short Notes	Item Status

Bathroom- Master 1	DISCOUNT>>Other	Sub Total:	\$-3,298.28
Location	Item Name	Short Notes	Item Status
Section: SUN CITY			
		Sub Total:	\$3,230.35
Bathroom- Master 1	BATHROOM PLUMBING >> FAUCET >> LABOR ONLY INSTALL FAUCET TO EXISTING LINES >>		Item Deleted (Change Order 2, 4/15/2021)
Bathroom- Master 1	BATHROOM PLUMBING >> TUB >> PLUMBING - INSTALL TUB>>Other		
Bathroom- Master 1	BATHROOM PLUMBING >> Roughed in Plumbing >> ROUGH IN TUB DRAIN AND SUPPLY LINES >>		
Bathroom- Master 1	BATHROOM PLUMBING >> Roughed in Plumbing >> ROUGH IN SHOWER VALVE (New location) >>		
Bathroom- Master 1	BATHROOM PLUMBING >> FINISH TRIM ITEMS LABOR >> VALVE COVER >>		
Bathroom- Master 1	BATHROOM PLUMBING >> FINISH TRIM ITEMS LABOR >> SHOWER HEAD >>		
Bathroom- Master 1	BATHROOM PLUMBING >> TOILET >> LABOR TO INSTALL TOILET INCLUDES NEW 1/4 STEEL FLEX WATER SUPPLY WITH BRASS FITTING AND WAX RING. >>		
Bathroom- Master 1	BATHROOM PLUMBING >> SINK >> LABOR ONLY NEW P TRAP AND BRAIDED STAINLESS STEEL FLEX LINES WITH ANGLE STOPS TO EXISTING DRAIN AND SUPPLY LINES >>		